

Implementation of Press-Brake-Formed Steel Tub Girders

March 7, 2024

Karl Barth, Ph.D.,
West Virginia University
Dept. of Civil & Env. Engineering





So why do we need a different solution?


“Doing the same thing over and over and expecting different results is insanity”

Albert Einstein

- Prestressed concrete box beams have been the standard solution since the 1970's for off-system, local agency, non-interstate bridges.
- MDOT study of current inventory shows pre-stressed concrete box beam service life < 50 years
- “Bridge engineers need improved design options so they can deliver bridges that are operational for 100 years or more”, FHWA

1970 + 50 years = NOW!

Superstructure Deterioration (MDOT)




4 - POOR CONDITION - structural capacity of element is affected or jeopardized by advanced deterioration, section loss, spalling, cracking, or other deficiency

3 - SERIOUS CONDITION - loss of section, deterioration, spalling, or scour have seriously affected primary structural components. Local failures are possible.

Proposed PBFTG System

- Bridge Technology Center:
 - Modules with steel press-brake tub girders
 - Galvanized or Weathering
 - Modules are joined using UHPC longitudinal closure pours
 - Modules can be shipped to site pre-topped with concrete or with a variety of other deck options



Experimental Testing



Experimental Testing (cont'd)



Noncomposite Section Capacity

- Global lateral-torsional buckling will govern for the proposed system:

$$M_{cr} = \frac{\pi^2 EI_y \beta_x}{2L^2} \left[1 \pm \sqrt{1 + \frac{4}{\beta_x^2} \left(\frac{GJL^2}{\pi^2 EI_y} + \frac{C_w}{I_y} \right)} \right]$$

- Note the “±” results from the direction of applied moment:
 - Section is stronger if the larger flange is in compression


Experimental = 95.0 kip
Theoretical = 92.3 kip



Modular Unit Specimen Construction



Modular Unit Fatigue Loading (67.43 kip, 0.75 Hz Frequency)



Press-Brake-Formed Tub Girders



External Reusable Formwork




Rebar Layout



Deck Pour



Modular Unit “Dry” Fit



Super and Skew



Aerial Views



Delivery of Modular Units



Modular Unit Placement




Fourteenmile Creek in Ranger, WV



Second Unit Placement



Girders Set and Formed



UHPC Pour



2021 AASHTO Focus Technology



NATIONAL RECOGNITION WITH THE AASHTO INNOVATION INITIATIVE AWARD

- 2020 Press-Brake Tub Girders receive the “2020 Innovation Award” as **a ready-to-implement technology** that offers improved performance/effectiveness, and have been demonstrated in "real world" applications.
- 2021 Press-Brake Tub Girders become a 2021 AASHTO Focus Technology
- 2023 Press-Brake Tub Girders to be included in revisions to the 10th Edition of the AASHTO LRFD Bridge Design Specifications. The revisions apply to Specification Equation 6.11.2.2-3, allowing DOTs, Counties and other entities to utilize AASHTO design guidelines instead of rewriting specifications to include U-BEAMS


“This is great news for state and local Departments of Transportation that are looking for economical, sustainable and accelerated construction solutions for short span bridges, which make up over half of the U.S. bridge inventory.”

- Karl Barth, Ph.D., Associate Professor of Civil and Environmental Engineering at West Virginia University in a recent [SSSBA article](#) about the revisions

Valmont Manufacturing Innovation

STATE OF THE ART PRESS BRAKE FABRICATION FACILITY:

- AISC intermediate bridge fabricator certification
- Patent pending manufacturing techniques
- increased production capacity by 5
- Total Capitol investment \$20M
- Cut production time by 70%
- U-beam™ facility fully staffed with new personnel
- Designed for manufacturing efficiency and reduced carbon emissions



Valmont Manufacturing Innovation

STATE OF THE ART PRESS BRAKE FABRICATION FACILITY:

- ✓ Open to production August 2021
- ✓ 2000 Ton 60' Press Brake
- ✓ Roll form camber capabilities
- ✓ Automated stud welding capabilities
- ✓ Safe and efficient material handling
- ✓ AISC IBR bridge fabrication certification



ROLL CAMBER PROCESS



60' PRESS BRAKE




AUTOMATED STUD WELDING



FINISH WELD STATION

The Valmont U-BEAM™ (a press brake formed steel tub girder)



**ONLY 5 SIMPLE FABRICATON
PROCEDURES ALL FOLLOW AASHTO
CONSTRUCTION SPECIFICATIONS:**

1. Material
2. Press-Brake Forming
3. Camber
4. Welding
5. Protective Coating



#1 AASHTO STEEL PLATE MATERIAL

AASHTO 11.3.1.2

AASHTO M270. Made in the USA. Steel Plates and Structural Shapes shall conform to ASTM A709/A709M.



#2 AASHTO FORMING

AASHTO 11.4.3.3 - Bent Plates
Fracture-critical and Non-fracture critical plates and bars shall be cold bent.



#3 AASHTO CAMBERING

AASHTO 11.4.12.2.7

Cold cambering is a customary means of achieving camber...to avoid impact damage to the steel, is appropriate to introduce bending pressure in a controlled fashion.





#4 AASHTO WELDING AND SHEAR STUDS

AASHTO 11.3.3

Certified Welders and welded stud shear connectors shall satisfy all requirements of the AASHTO/AWS D1.5M/D1.5 Bridge Welding Code related to material, manufacturing, physical properties, certification, and welding.

#5 AASHTO PROTECTIVE COATING


AASHTO 11.3.7

Galvanizing shall be in accordance with AASHTO M 111M/M 111 (ASTM A123/A123M)



Continuous Span applications: link slabs

- Full scale link slab between two modular steel tub girders




2021 MDOT GRAND TRAVERSE COUNTY




Latest Installation, Grand Traverse County, MI

- Consultant designed as precast concrete bridge deck



Latest Installation, Grand Traverse County, MI

- Contractor chose to VECP cast-in-place deck option



Grand Traverse County, MI Installation

Consultant designed as precast concrete bridge deck, contractor chose to VECP cast-in-place deck option



The Boardman River is considered one of the top ten trout streams in Michigan

Grand Traverse County, MI Installation

2 Span cast-in-place deck, open to traffic 2 week after U-BEAMs delivered



Grand Traverse County, MI Finished Product

Finished Product, August 2021



2 Span Bridge Beams

Continuous Bridge Deck